

PROCEDURE FOR PREVENTING WALKWAY/DOCKS FROM FLOATING FREE

As outlined in our cyclone plan, should it be deemed necessary to prevent the walkways/docks from floating free the following procedure can be implemented.



Remove the white pile caps to gain access to the chain located inside.



Lengths of timber are to be secured to the top of each pile by fastening the chain with either a D shackle, snap shackle or small length of rope.

Use a baton screw to secure a chain link into the timber length to prevent movement.

All necessary items can be found in the maintenance shed.

